



NOTES:

1. APRON SHALL BE CONSTRUCTED A MINIMUM OF 18 FEET FROM THE EDGE OF ROAD.
2. PAVEMENT SECTION TO BE 7 INCHES THICK NON-REINFORCED CONCRETE MDOT SHA MIX NO. 9 OR 1.5 INCHES HOT MIX SUPERPAVE 9.5 MM FOR SURFACE (PG 64S-22, LEVEL 1), 3.0 INCHES HOT MIX SUPERPAVE 19.0 MM FOR BASE (PG 64S-22, LEVEL 1), AND 6.0 INCHES GRADED AGGREGATE BASE (GAB).
3. COUNTY APPROVAL REQUIRED FOR ANY DESIGN MODIFICATIONS TO THIS DETAIL.
4. INSTALL EXPANSION JOINTS AND FLARE CORNERS TO PREVENT BREAKAGE.
5. SIDEWALK SHALL BE BUILT IN ACCORDANCE WITH CURRENT ADA STANDARDS.

CARROLL COUNTY, MARYLAND DEPARTMENT OF PLANNING AND LAND MANAGEMENT	USE IN COMMON DRIVEWAY APRON WITH CURB AND GUTTER	PLATE NO.
		UIC 9
ISSUED:	REVISED:	
REVISED:	REVISED:	